



DEVELOPMENT SERVICES

1112 Manatee Ave, 4th Floor, Bradenton, FL 34205
(941) 742-4190

Recommended Hurricane Preparedness Procedures for Construction Sites

- A. This recommended checklist is intended to assist you in making your job site safe during a hurricane event.
- B. Preparations must be completed **48 hours** in advance of landfall of a hurricane warning for Manatee County.
 1. Site Preparation
 - Clean site of loose materials to minimize flying debris.
 - Tie down job trailers and portable structures (including toilets).
 - Secure lids of dumpsters.
 - Brace new landscaping.
 - Remove sand /trash from roadway gutters and drainage systems.
 - Remove construction vehicles and equipment or move inside.
 2. Construction Materials
 - Band and stake down plywood lumber, scaffolding, etc.
 - All materials inside buildings should be banded together.
 - Remove all wood scraps around trailers and site.
 3. Roofing Materials
 - Do not load tile onto roof if it cannot be installed 48 hours prior to predicted landfall.
 - Remove and secure roof materials prior to 48 hours prior to predicted landfall.
 4. Structural building elements
 - Shore up unsupported walls, frame or block.
 - Inspect trusses to ensure anchors and hurricane clips are in place.
 - Plywood not installed should be removed to the ground.
 - Lower tower cranes if possible.
 - Inspect tie down on construction and sales trailers.
 - Secure any antennas.
 5. Windows and glass
 - If possible, install panels over windows and sliding glass doors.
 - Secure all windows and doors.